

The K computer: Project overview

SHOJI, Fumiyoshi

Next-Generation Supercomputer R&D Center,

RIKEN



- ✓ Project Overview
- ✓ System Configuration of the "K computer"
- ✓ Facilities for the system






- ✓ Project Overview
- ✓ System Configuration of the "K computer"
- √ Facilities for the system





What is "K computer"?

- ✓ "京 (Kei)" is a nickname of the Next-Generation Supercomputer system.
 - ✓ The name was chosen from public applications this July.
 - \checkmark "京" is a Japanese prefix number like "mega, tera, peta, etc.", which means 10^{16} , or 10 peta.
 - "万(man)=10⁴", "億(oku)=10⁸", "兆(cho)=10¹²", "垓(gai)=10²⁰", • •



- ✓ A logo 🐔 was also determined.
 - ✓It was written by a famous Japanese calligrapher Souun TAKEDA.
- ✓ Another meaning of the "京" is "a big gate."
 - ✓ A new era of computational science is coming though the gate "京." by hoping promised future success.







Goals of the Next-Generation Supercomputer project

- ✓ Development and installation of the most advanced high performance supercomputer system with LINPACK performance of 10 petaflops.
- ✓ Development and deployment of application software, which should be made to attain the system maximum capability, in various science and engineering fields.
- ✓ Establishment of an "Advanced Institute for Computational Science:AICS" as one of the Center of Excellence around supercomputing facilities.
- →The AICS has been established in Kobe at October 2010.

Schedule of the project

We are here.

		FY2006	FY2007	FY2008	FY2009	FY201	0	FY2011	FY2012
System		Conceptual Detailed design			Prototype, evaluation			on, installation, djustment	Tuning and improvement
Applications	Next-Generation Integrated Nanoscience Simulation	Development, production, and evaluation						Verification	
	Next-Generation Integrated Life Simulation	Development, production, and evaluation						Verification	
Buildings	Computer building		Design Construction						
	Research building		Design Construction						



First installation of the K computer

- ✓ The eight racks has been housed at October 1, 2010.
- ✓ First Linpack result by a part of the system
 - ✓ Rmax:48.03TFLOPS(Rpeak:52.22TFLOPS)
 - ✓ Power:57.96kW






- ✓ Project Overview
- ✓ System Configuration of the "K computer"
- ✓ Facilities for the system






System configuration



CPU features (Fujitsu SPARC64TM VIIIfx)

- √ 8 cores
- ✓ 2 SIMD operation units/core
 - ✓ 2 Multiply & add floating-point operations (SP or DP) are executed in one SIMD instruction
- ✓ 256 FP registers/core (double precision)
- ✓ Performance
 - ✓ 16GFLOPS/core, 128GFLOPS/CPU
 - ✓ 2.2GFLOPS/W (58W at 30°C by water cooling)
- ✓ Hardware barrier among cores
- ✓ Pre-fetch instruction
- ✓ Shared 6MB L2 Cache (12-way)
 - ✓ Software controllable cache (sectored cache)

Reference: SPARC64TM VIIIfx Extensions http://img.jp.fujitsu.com/downloads/jp/jhpc/sparc64viiifx-extensions.pdf




45nm CMOS process, 2GHz 22.7mm x 22.6mm 760 M transistors



Compute nodes and Network

- Compute nodes (CPUs): > 80,000
 - Number of cores: > 640,000
- Peak performance: > 10PFLOPS
- Memory: > 1PB (16GB/node)

- 6-dimensional mesh/torus network: Tofu
 - 10 connections to each adjacent node
- Peak bandwidth: 5GB/s x 2 for each connection
- Logically 3-dimensional torus network





Packaging of the system

A rack consists of 24 system boards, 6 IO boards, power supply units, system storages, and diagnostic processors. 796mm A hose pipe is connected to the water loop under the floor. System Board 2060mm LSI for interconnect ~460mm

RIKEN Advanced Institute for Computational Science

- ✓ Project Overview
- ✓ System Configuration of the "K computer"
- ✓ Facilities for the system





AICS: location of the K computer in Kobe



450km (280miles) west from Tokyo



AICS (Advanced Institute for Computational Science) was

Layout of the buildings



Image of the K computer





The full system will be in operational in 2012.



Summary

- ✓ "The Next-Generation Supercomputer"
 - → "京(kei)", "K computer"
- ✓ The facilities for the K computer is complete.
- ✓ The installation of the K computer has started.



✓ The full system of the K computer will be in operational at 2012.





Thank you for your attention!

