

Installation Pack

Technical Appendix for Eternus DX

We install what we support – Help in getting started with Eternus DX

The Technical Appendix supplements the general data sheet "Installation Pack – Installation services for Fujitsu Server and Storage Systems" and describes the specific services for the ETERNUS DX disk storage products from Fujitsu. The prerequisites described in the respective installation manuals must be taken into consideration.

The Installation Pack for ETERNUS DX disk storage is offered in two different versions - Single or Multiple. In both versions the installation takes place according to the manufacturer's specifications.

Scope of service:

The service for the ETERNUS DX system to be installed covers the basic system unit and the expansion shelves, if the installation services have also been commissioned for them.

Likewise the installation of controllers and disk drives is included if they have not already been installed at the factory. If the systems were already pre-installed in a rack at the factory, the installation and connection of the rack is also included.

All the services listed below are available when purchasing an installation offering, the customer does not need to take all options and can select any applicable services, but all are available at the same price.

The service described in the data sheet apply for the ETERNUS DX as follows:

1. Unpacking and verification of the supplied components.
2. Installation of the hardware in the rack or, as the case may be, installation of the rack with the components that were pre-installed at the factory.
3. Establishment of the internal physical connections in the system or to the expansion shelves according to the manufacturer's specifications.
4. Initial system power-up.
5. Execution of the diagnostic routines recommended by the manufacturer.
6. Check whether the firmware is up to date and where necessary, upgrade to latest version.
7. Configuration of the administrator access from the network.
8. Configuration of the system with the setup of a host connection according to customer specifications and the setup of a RAID group with a LUN in order to ensure functionality. This does not include any possibly required Zoning or SAN configuration.
9. Function test: Initial system power-up and the internal self-tests were completed without failure. The test LUN is accessible from the test server.